तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

चेतनाथ गिरी
प्रमुख प्रशासकीय अधिकृत

आयोजनाको नाम: जनता मा.वि. होस्टेल देखि चौपारी सम्म ढल निर्माण+ पाल्पा आवासीय क्षेत्र बाट मिसन जाने बाटो ३ न सिमाना माथि पट्टि सम्म

Place of implementation of the project: Tansen-03,

सम्पन्न हुने अनुमानित अवधि:.....

Fiscal Year: 2083-084

बजेट उप शीर्षक न:

S.N	Standard specification of roads and bridges	Description of Work Item	Unit	Quantity	Rate	Rate in Words	Remarks
१		२	३		५	६=४x५	७
A		Provisinal Sum Work					
1	110(DOR)	Supply and installation of Project sign board for construction Information.	NO	2.00			
B		Construction Work					
1	202(DOR)	प्लेन सिमेन्ट कङ्क्रीट वा वज्र कंक्रीट भत्काई त्यसबाट आएको सामग्री	cum	0.69			
2	905(DOR)	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterous matter, all lift and leads as per Drawing and Instruction of the Engineer.	cum	3.72			
3	1201(DOR)	जगको खाडलमा ढुंगा भर्ने र लेभल गर्ने काम ३० मीटरसम्म ढुवानी सहित ।	cum	1.41			
5	2000(DOR)	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications.	cum	1.72			

तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

आयोजनाको नाम: जनता मा.वि. होस्टेल देखि चौपारी सम्म ढल निर्माण+ पाल्पा आवासीय क्षेत्र बाट मिसन जाने बाटो ३ न सिमाना माथि पट्टि सम्म

Place of Implementation of the project: Tansen-03,

सम्पन्न हुने अनुमानित अवधि:.....

Fiscal Year: 2080-084

बजेट उप शीर्षक न:

S.N	Standard specification of roads and bridges	Description of Work Item	Unit	Quantity	Rate	Rate in Words	Remarks
	2000(DOR)	PCC works in M20 (1:1.5:3) using crusher aggregate & Use in machine mixed concrete Including mixing, placing, compaction, cleaning with wire brush and water in old concrete surface for laying new concrete and curing with all complete works. (repair in Exting water supply and Sanitary pipe Under Construction).Using Concrete Mixture and including formworks	cum	12.11			
6	2500(DOR)	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	cum	0.14			
7	620(DOR)	Providing and laying, fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg	2.40			

तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

आयोजनाको नाम: जनता मा.वि. होस्टेल देखि चौपारी सम्म ढल निर्माण+ पाल्पा आवासीय क्षेत्र बाट मिसन जाने बाटो ३ न सिमाना माथि पट्टि सम्म

Place of implementation of the project: Tansen-03,

सम्पन्न हुने अनुमानित अवधि:.....

प्रमुख प्रशासकीय अधिकृत

Fiscal Year: 2083-084

बजेट उप शीर्षक नं:

S.N	Standard specification of roads and bridges	Description of Work Item	Unit	Quantity	Rate	Rate in Words	Remarks
8	701(DOR)	Providing and Laying 8" (200mm) HDPE pipe for drainage including as and technical specifications with all complete work	RM	22.85			
					जम्मा लागत अनुमान रकम रु.		
					VAT 13%		
					जम्मा रकम रु.		