

Ichchhakamana Rural Municipality
Office of Rural Municipality

Kurintar, Chitwan
Bagmati Province, Nepal
Bill of Quantity

योजनाको नाम: इच्छाकामना सिद्धबाबा मन्दिर पूर्वाधार निर्माण

स्थान: इच्छाकामना वडा नं. ५, इच्छाकामना मन्दिर

Tender identification: Qutation



आर्थिक वर्ष: २०८३/२०८४

S.N.	Particulars	Quantity	Unit	Rate		Amount	Remarks
				In figure	In words		
A							
Civil Works							
1	Earth work in Excavation Hard clay with soft stone	216.00	Cft				
2	Backfilling Work with compaction	86.40	Cft				
3	Stone Soling Work	63.00	Cft				
4	Lime Concrete in Foundation and wall in (1:2:4) lime, sand and aggregate.	31.50	Cft				
5	Stone work in foundation in cement sand 1:4 ratio	225.72	Cft				
6	Chimney Brick work in (1:1:2) lime,surkhi, sand mortar for ground floor	375.75	Cft				
7	Sal Timber work for chaukhat frame (up to 8'-0")	10.62	Cft				
8	Wood plane shutter gain and khur	21.00	sqf				
9	Traditional Brick (Small Dachi Appa)size 210x55x97 mm work in (1:1:2) lime,surkhi, sand mortar	492.00	sqf				
10	Traditional Kassimo Brick work in (1:1:2) lime,surkhi, sand mortar	81.00	ftt				
11	Traditional Nago Brick work in (1:1:2) lime,surkhi, sand mortar	24.00	ftt				
12	Telia Brick (Machine made) 6"x6" in (1:1:1) lime, surkhi,sand mortar with (1:1) lime surkhi pointing	40.50	sqf				

Prepared By:

Checked By :

Approved By:

Ichchhakamana Rural Municipality
Office of Rural Municipality

Kurintar, Chitwan

Bagmati Province, Nepal

Bill of Quantity



योजनाको नाम: इच्छाकामना सिद्धबाबा मन्दिर पूर्वाधार निर्माण

स्थान: इच्छाकामना वडा नं. ५, इच्छाकामना मन्दिर

Tender identification: Qutation

आर्थिक वर्ष: २०८३-२०८४

S.N.	Particulars	Quantity	Unit	Rate		Amount	Remarks
				In figure	In words		
13	Traditional palefo Brick work in (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	40.50	ft				
14	Traditional Ba fya Brick work in (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	40.50	ft				
15	Traditional fya Brick work in (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	40.50	ft				
16	Traditional sinkhwa 4" Brick with astamangal or full butta work in (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	40.50	ft				
17	4" Peti Stone (10" X4") work in (1:1:1) lime, surkhi, sand mortar	12.00	sqf				
18	Flush pointing in (1:1:2) lime, surkhi, sand on Brick wall.	259.50	sqf				
19	Single MS black pipe Scaffolding works	504.00	sqf				
20	Site Clearance Work	1.00	ls				
21	हुवानी गर्ने काम काठमाडौं देखि इच्छाकामना मन्दिर सम्म	1.00	job				
Sub Total of B							
Vat -13%							
Grand Total							

Handwritten signature

Prepared By:

Checked By:

Approved By:

Handwritten signature