तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

चेतनाथ गिरी
प्रमुख प्रशासकीय अधिकृत

आयोजनाको नाम: निशान धारा खानेपनि धारा तथा क्रियापुत्री भवन मर्मत कार्य + निशान धारा सौन्दर्यकरण

Fiscal Year: 2083-084

स्थान: ता.न.पा. ०३

बजेट उप शीर्षक न:

सम्पन्न हुने अनुमानित अवधि:.....

S.N	Standard Specification of roads and bridges	Description of Work Item	Unit	Total Quantity	Rate	Rate in Words	Remarks
१		२	३		५	६=४x५	७
A		Provisional sum					
१	511(DOR)	Carrying out additional laboratory tests for materials and works as required and instructed by the Engineer.	ps	1.00	2590.00	2590.00	
B		General work					
1	110(DOR)	Supplying and installation of Project Signboard including all the fittings as per technical specification .	Cum	2.00			
C		Construction Work					
	201(DOR)	घाँस काट्ने त्यसको जरा झिक्ने, ढिस्को फुटाउने र लेभल गरी स्थल सफा गर्ने सबै वोकनी समेत	sqm	25.00			
1	905(DOR)	Excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterous matter, all lift and leads as per Drawing and Instruction of the Engineer.	Cum	26.41			

तानसेन नगरपालिका

नगर कार्यपालिकाको कार्यालय

२०७३ लुम्बिनी प्रदेश ,पाल्पा

BOQ

आयोजनाको नाम: निशान धारा खानेपनि धारा तथा क्रियापुत्री भवन मर्मत कार्य + निशान धारा सौन्दर्यकरण

स्थान: ता.न.पा. ०३

सम्पन्न हुने अनुमानित अवधि:.....

देवराज गिरी
प्रमुख प्रशासकीय अधिकृत

Fiscal Year: 2083-084

बजेट उप शीर्षक न:

S.N	Standard Specification of roads and bridges	Description of Work	Unit	Total Quantity	Rate	Rate in Words	Remarks
		Item					
2	1201(DOR)	जगको खाडलमा ढुंगा भर्ने र लेभल गर्ने काम ३० मीटरसम्म ढुवानी सहित	Cum	5.86			
3	2000(DOR)	Providing and laying of PCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications.	sqm	8.79			
4	2500(DOR)	Brick Masonary work in 1:4 cement sand mortar with line, level, with proper curing with all complete as per the Site Engineer and specification.	sqm	9.56			
5	2510(DOR)	Cement Plaster work in wall 1:4 cement sand mortar with line, level, with proper curing with all complete as per the Site Engineer and specification.	sqm	108.45			
6		Two coat Exterior weather paint with Prime Coat with all complete as per the Site Engineer and specification.	sqm	108.45			

तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

चेतनाथ गिरी
प्रमुख प्रशासकीय अधिकृत

आयोजनाको नाम: निशान धारा खानेपनि धारा तथा क्रियापुत्री भवन मर्मत कार्य + निशान धारा सौन्दर्यकरण

स्थान: ता.न.पा. ०३

सम्पन्न हुने अनुमानित अवधि:.....

Fiscal Year: 2083-084

बजेट उप शीर्षक न:

S.N	Standard Specification of roads and bridges	Description of Work Item	Unit	Total Quantity	Rate	Rate in Words	Remarks
7	620(DOR)	५० मी.मी.व्यासको स्टेन्लेसस्टिलको ह्याण्डरेलमा २ मिटरको दूरीमा ५० मी.मी.व्यासको स्टेन्लेसस्टिलकै ठाडो पोष्ट राखी ह्याण्डरेल र भूइंको बीचमा तीन तह तेर्सो २५ मी.मी.व्यासको स्टेन्लेसस्टिलको मेम्बर राखी २'-६" देखि ३'-०" सम्म उचाई भएको रेलिङ्ग उपलब्ध गराई जडान गरी रंग समेत लगाउने काम ।	RM	30.80			
8		UPVC Door having frame(69/58mm) inside 1.5mm galvanized reinforcement with 5mm clear normal glass including cost of material, labor & fitting all Complete Work	Sqft.	27.12			
9		UPVC Sliding having frame(80/58mm) window sash(38/62mm), 2.5mm wall thk inside 1.5mm galvanized reinforcement with 5mm clear normal glass including cost of material, labor & fitting all Complete Work	Sqft.	6.89			
10		सामान सहित सर्फेस वायारिंग गर्ने कार्य	Point	7.00			

तानसेन नगरपालिका
नगर कार्यपालिकाको कार्यालय
लुम्बिनी प्रदेश ,पाल्पा

BOQ

चेतनाथ गिरी
प्रमुख प्रशासकीय अधिकृत

आयोजनाको नाम: निशान धारा खानेपनि धारा तथा क्रियापुत्री भवन मर्मत कार्य + निशान धारा सौन्दर्यकरण

स्थान: ता.न.पा. ०३

Fiscal Year: 2083-084

बजेट उप शीर्षक न:

सम्पन्न हुने अनुमानित अवधि:.....

S.N	Standard Specification of roads and bridges	Description of Work Item	Unit	Total Quantity	Rate	Rate in Words	Remarks
11		Supplying and installation of LED Blub 9 watt warrenty including all the fittings as per technical specification.	no.	4.00			
12		Supplying and laying of ceiling fan (48") usha, bajaj including all the fittings as per technical specification	no	1.00			
					Total estimated amount		
					VAT 13 %		
					Grand Total		