Tulsipur Submetropolitan City

Office of the Municipal Executive

Tulsipur, Dang District

Lumbini Province, Nepal

Invitation for Bids

Invitation for Bids No: TSMC/NCB/W/2083/84-10

Date of publication: 10/29/2026

1. *Tulsipur Submetropolitan City, Office of the Municipal Executive* invites sealed bids from Nepalese eligible bidders for the construction of *Kataha Beltakura Sadak Pakki Nala ra Kalopatre* under National Competitive Bidding procedures. The estimated amount for the works is NRs. 4317010.54/-*(without VAT & Contingency but including PS).*
2. Eligible Bidders may obtain further information and inspect the bidding documents at the office of Tulsipur Submetropolitan City, Office of the Municipal Executive, Tulsipur, Dang, email: info@tulsipurmun.gov.np Cont. 082-520233.
3. A complete *set* of Bidding Documents may be purchased from the office *Tulsipur Submetropolitan City, Office of the Municipal Executive.* (तुलसीपुर उपमहानगरपालिका, नगर कार्यपालिकाको कार्यालय), Tulsipur, Dang and the office Area Administration Office(इलाका प्रशासन कार्यालय),Tulsipur, Dang, by eligible Bidders on the submission of a written application, along with the copy of company/firm registration certificate, and upon payment of a non-refundable fee of NPR *3000/-* till *11/18/2026* during office hours *in the account as specified below.*

   Information to deposit the cost of bidding document in Bank:

   Name of the Bank: Nepal Investment Mega Bank Ltd.
   Account Name: Tulsipur Sub-Metropolitan city,Office of the Municipal Excutive
   Account Number: 03101400250092
   Branch: Tulsipur, Dang
4. Pre-bid meeting shall be held at *Tulsipur Submetropolitan City, Office of the Municipal Executive., Tulsipur, Dang* at *11/6/2026, 11.00 AM.*
5. Sealed must be submitted to the office *Tulsipur Submetropolitan City, Office of the Municipal Executive., Tulsipur, Dang* by mail/(हुलाक) by hand or by courier on or before *12:00:00 Noon* on *11/19/2026*. Bids received after this deadline will be rejected.
6. The bids will be opened in the presence of Bidders' representatives who choose to attend at *11/19/2026, 2:00:00 PM* at the office of *Tulsipur, Dang*. Bids must be valid for a period of *90 Day* from the bid submission deadline and must be accompanied by a bid security or scanned copy of the bid security in pdf format in case of e-bid, amounting to a minimum of NPR. *108000/-*, which shall be valid for 30 days beyond the validity period of the bid (i.e. *3/18/2027*) If bidder wishes to submit the Cash Security, the cash should be deposited in Deposit Account No. 03101400250030 at Nepal Investment Mega Bank Ltd.Tulsipur Dang and submit the receipt of the deposited amount of cash along with the bid documents.
7. If the last date of purchasing and /or submission falls on a government holiday, then the next working day shall be considered as the last date. In such case the validity period of the bid and bid security shall remain the same as specified for the original last date of bid submission.

२०८३।०६।१९

Bill of Quantities

Sl.No.	Item Description	Unit	Qty	Rate(NRs)	Rate in Words	Amount(NRs)
1	Supplying and installation of hording board specifying brief of project as per specified size, shape and instruction of site incharge all complete.	PS	1.0	5,000.00	**five thousands**	**5,000.00**
2	Insurance premium for the works, plants, equipment, material damage contractor's workmen and employees and third party insurance against damage to other persons and property for the contract period along with defect liability period (DLP) .	PS	1.0	20,000.00	**twenty thousands**	**20,000.00**
3	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.0	30,000.00	**thirty thousands**	**30,000.00**
					Total	**55,000.00**

2 Construction Work

2.1 Pavement , Drain,Culvert & Stone Masonary Works

Procument Item Details

Sl.No.	Item Description	Unit	Qty	Rate(NRs)	Rate in Words	Amount(NRs)
1	Scarifying the existing road surface by mechanical means to a depth of 50 mm and disposal of scarified material with all lifts and leads as per Drawing and Technical Specification.	sq.m	2289.75			
2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	cu.m	343.46			
3	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of base course as per Drawing and technical Specifications.	cu.m	302.93			

4	Providing and Applying Prime coat with hot bitumen (including Cutter) of grade VG 30 on the prepared surface of granular base including cleaning of road surface and spraying at specified rate by mechanical means as per the Technical Specification.	ltr	2019.50			
5	Providing and Applying Tack coat with hot paving grade VG 30 bitumen by mechanical means at specified rate on the prepared surface including cleaning as per the Technical Specification.	ltr	952.05			
6	Providing and laying open-graded premix carpet of 20 mm thickness (mechanical means) composed of 13.2 mm to 5.6 mm aggregates as wearing course on a previously prepared base as per drawing and Technical Specifications.	cu.m	34.62			
7	Providing and laying Coarse sand seal coat sealing the voids in a bituminous surface as per Drawing and Technical Specifications.	sq.m	1731.00			
8	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterous matter, all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means)	cu.m	30.94			
9	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms)	cu.m	8.25			
10	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications	cu.m	4.24			
11	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications including form works all complete. (2000)	cu.m	20.97			

12	Providing and laying, fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications (SS Clause 2014)	kg	1123.82			
13	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	cu.m	6.00			
14	60 cm dia NP3 RCC Humpipe With Transportation	Rm	15.00			
15	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	cu.m	8.78			
					Total	

Total of Procument Items	
Total Item Price	
VAT	
Grand Total	