

[Signature]

गौरिगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल



[Signature]

(M35, NS Standard)
(Blended calas)

योजनाको नाम: चौमाला बहुमुखी क्याम्पसको परिसरमा पार्केटिङ ब्लक विछाने
स्थान:- गौरिगंगा-०१, कैलाली

BILL OF QUANTITIES

Contract IDNo.: - GGM/WORKS/SO/02/2083/084

SN	Description of Works	Unit	Total Quantity	Rate (Nrs)		Amount (Nrs)	Remarks
				Rate in Figure	Rate in Words		
1	Scarifying Existing road Surface to a Depth of 50 mm by Manual Means. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	m2	75				
2	Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means .	M3	1.5				
3	Providing, laying, Soil with borrow material as per Drawing and Technical Specifications.	m3	36				
4	Providing and laying of 60 mm thick heavy-duty Hexagonal Interlocking Pavers , Blended colour, M35 or above, size (200 × 226)×60 mm, conforming to NS Standard, over a properly prepared and compacted 60 mm thick crusher dust bedding layer. The work shall include surface preparation, laying to required line, level and slope, cutting and fitting at edges, joint filling, vibration/compaction, finishing and cleaning, complete as per Drawing and Technical Specifications	m2	688.5				
B			Sub Total				
1	Off site verification Lab testing of materials as required by the engineer's representative	PS	1.00	2500.00			2500.00
2	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	Ps	1.00	1000.00			1000.00
			Sub Total				3500.00
			Total				
				Vat @ 13% of Total			
				Grand Total			

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

Phone :

Date :