


[Signature]

Name of Project :-मछालापट्टि सडक कालोचरे
Location :-गोरिगंगा-०९, कैलाली
Contract ID :-GGM/WORKS/SG/03/2083/084

गोरिगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल



BOQ

S.no.	Description	Unit	Quantity	Rate NRs.		Total Amount	Remarks
				Rate in figure	Rate in words		
1	Scarifying Existing road Surface to a Depth of 50 mm by Manual Means. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	m2	586.250				
2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means.	m3	18.000				
4	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	m3	2.81				
5	Excavation For Cross Drainage Works in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means.	m3	4.500				
6	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	1.125				
7	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	m3	1.125				
8	Providing and lying Stone Masonry work in cement mortar 1:6 in structure complete as per Drawing and Technical Specifications Random Rubble Masonry	m3	7.509375				
9	Providing and laying granular Sub-Base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means	m3	71.188				
10	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of Base Course as per drawing and technical specifications.	m3	67.000				
11	Providing and applying Prime Coat with Hot Bitumen(including cutter) on prepared surface of granular base including cleaning of road surface and spraying at specified rate by manual means as per Technical Specification .Prime Coat, with MC 30 / 70 by Bitumen , Mechanical Means	Lit.	565.313				

[Signature]

Name of Project :-सुदूरपश्चिम प्रदेश, कैलाली
Location :-गौरीगंगा-०९, कैलाली
Contract ID :- (66M/WORKS/SR/03/2083/084

BOQ

गौरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल
गौरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चौमाला, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल
२०७३

S.no.	Description	Unit	Quantity	Rate NRs.		Total Amount	Remarks
				Rate in figure	Rate in words		
12	Providing and applying Tack Coat with hot Bitumen at the specified rate the prepared surfaces including cleaning as per Technical Speciation. Tack coat with Bitumen By Mechanical Means	Lit.	314.063				
13	Providing and laying open-graded Premix Carpet of 20 mm thickness using Bituminous (Paving bitumen / Modified bitumen) Binder. composed of 13.2 mm to 5.6 mm aggregates as wearing course on a previously prepared base as per drawing and Technical Specifications. Mechanical method using Hot Mix Plant	m3	12.563				
14	Seal Surfacing Providing and laying seal coat sealing the voids along with Rolling in a bituminous surface as per Drawing and Technical Specifications.	m2	628.125				
Part 5 : PROVISIONAL SUMS FOR							
5.1	Off site verification Lab testing of materials as required by the engineer's representative	PS	1.00	20000.00	Twenty Thousand only	20000.00	
5.2	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	PS	1.00	1500.00	Fifteen hundred Only	1500.00	
					Sub Total PS	21500	
					Sub total		
					Vat 13%		
					Grant Total With PS		

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

phone :

Date