



BOQ

NGM/WORKS/59/04/2083/084

योजनाको नाम:- चमारपुर दुर्गा प्रा. वि को पक्क पखाल निर्माण

ठेगाना:-गौरिगंगा-०८ कैलाली

F/Y:-2083/084

S. No.	Description of Items	Unit	Quantity	Rate NRs.		Amount (NRs.)	Remarks
				Rate in figure	Rate in words		
A.	Provisional Sum						
	Providing and installation of project signboards with size of 1.2 x 1.0 m as per specification and instruction of engineer [110]	PS	1.00	1500.00	Fifteen Hundred Only	1500.00	
	Off site verification Lab testing of materials as required by the engineer's representative	PS	1.00	5000.00	Five Thousand Only	5000.00	
					Sub total	6500.00	
B.	Civil Works						
1.00	Earthwork in excavation for foundation in gravel mixed and silty soils upto the required depth and disposal of excavated materials upto 10m lead and 1.50m lift including dressing of sides, ramming the bottom as per approval of site engineer.	Cu. m.	32.04				
2.00	Stone soling in foundation,wall and floor etc including leveling,compaction by labour.	Cu. m.	8.01				
3.00	Providiing, laying, compacting and curing plain cement concrete (1:3:6) in foundation with cement, sand and stone ballast 20mm gauge finishing to approved level, lines and dimensions all complete as per the instruction of the site engineer.	Cu. m.	5.03				
4.00	1st Class Brick masonry work in 1:6 C/S mortar including supplying height up to 5.00 m	cum	26.49				
5.00	Stone masonry work in 1:6 C/S mortar including supplying hard block & bond stone, masonry	Cum	27.03				
6.00	12.5mm. thick cement sand plaster 1:6 on walls (inner & outer wall surfaces).	Sq. m.	267.00				
			Sub-Total				
			Vat 13%				
			Grand Total With PS				

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

phone :

Date