

Bill of Quantities

Provisional Sum				
-----------------	--	--	--	--

Procurement Item Details				
Sl. No.	Item Description	Unit	Quantity	Unit Rate (NPR)
1	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	Ps	1.0	1000.0
2	Lab Test / Off site verification testing of materials as required by the engineer's representative	Ps	1.0	10000.0
				10,000.00
				1,000.00
				Amount (NPR)

2 Construction work

Procurement Item Details				
Sl. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of servicable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Manual Means, In area of light jungle (less than 15 number per 100 sqm)	m2	32.00	
2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means.	m3	78.04	
3	Providing suitable Locally available material and Back filling behind abutment, wing wall and return wall complete as per Drawing and technical specifications for including compaction by tamping rod (with waiting)	m3	15.75	
4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	17.06	
5	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	m3	13.81	
6	Providing and laying of Plain/Reinforced Cement Concrete M 20 (or 1:1.5:3 for nominal mix) in superstructure along with formworks	m3	24.08	
				Total Amount (NPR)
				Bidder's Rate (in words)

Faharam Bhulko Ghar dekhi Udasi Jane

Sadak ma Culvert Nirman Ra Pashupati

Ma.Vi. Pachhadi Chanaura Kulo ma Culvert

[Signature]



GGMWORKS/SQ/05/2083/084

[Signature]

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
	complete as per Drawing and Technical Specifications.					
7	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Technical Specifications. 60% M15 concrete and 40%Boulders/stone Using Mechanical Aids all complete	m3	91.21			
8	Providing . Preparing and Installing form work including necessary supports and removing after completion for walls.(Class F2 Finish), vertical plain surface Using timber and plywood.	m2	179.25			
9	Providing and laying Reinforcement including cutting, bending, binding, fixing in position &30m lead etc. all complete as per specification and drawing.	Kg	2,315.81			
10	Providing and laying and Spreading of Granular Gravel on prepared surface, Drawing and Technical Specifications	m3	75.07			
Total of Procurement Items						
Total Item Price						
VAT						
Grand Total						